

ILLEGIB

Approved For Release 2001/03/30 : CIA-RDP78T05439A000300300028-9

Next 1 Page(s) In Document Exempt

Approved For Release 2001/03/30 : CIA-RDP78T05439A000300300028-9

Approved For Release 2001/03/30 : CIA-RDP78-05439A000300380028-9


~~TOP SECRET~~

Copy  
6 Pages

NPIC/R-245 '64

April 1964

PHOTOGRAPHIC INTERPRETATION REPORT

**Declassification review by NIMA/DOD****ICBM COMPLEX, KOZELSK, USSR,  
LAUNCH AREAS A, B, AND D**

CIA




DIA

Handle Via **TALENT - KEYHOLE** Control Only**WARNING**

This document contains classified information affecting the national security of the United States within the meaning of the espionage laws U. S. Code Title 18, Sections 793 and 794. The law prohibits its transmission or the revelation of its contents in any manner to an unauthorized person, as well as its use in any manner prejudicial to the safety or interest of the United States or for the benefit of any foreign government to the detriment of the United States. It is to be seen only by personnel especially indoctrinated and authorized to receive TALENT-KEYHOLE information. Its security must be maintained in accordance with KEYHOLE and TALENT regulations.

NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER

~~TOP SECRET~~

TOP SECRET CHESSE RUFF

NPIC/R-245/64

# ICBM COMPLEX, KOZELSK, USSR, LAUNCH AREAS A, B, AND D

This report presents information on Launch Areas A, B, and D of the Kozelsk ICBM Complex based on KEYHOLE photography through [REDACTED] and updating that given in NPIC/R-267/63, dated November 1963. 1/

## LAUNCH AREA A

Launch Area A (53-54N 35-44E) consists of a completed Type IIC launch site and a site support facility located in a wooded area 3.5 nautical miles (nm) south-southwest of the complex support facility (Figures 1 and 2). The area was identified in [REDACTED] It cannot be negated. Construction was considered complete in [REDACTED] Ground snow cover in [REDACTED] obscures some object detail and road and launch-pad outlines.

The launch site is enclosed by security fencing. Each launch pad is flanked by two bunkers, and a tower-like structure projects from the left and larger bunker on the side adjacent to the pad. Three other possible bunkered objects are positioned left of the center service road, between the pads, and a smaller possible bunkered object is in front of the right pad.

An earth-banked missile-ready building is located in line with and approximately 900 feet behind each pad. These ready buildings probably are connected to their pads by four snow-cleared tracks which exit each ready building and appear to converge between the building and the pad. No tracks can be identified on the pads. There is one building located just to the right of the center service road to the rear of the site.



FIGURE 1. LAUNCH AREA A.


25X1D

TOP SECRET CHESSE RUFF

TOP SECRET CHESS RUFF

(NPIC/R-245/64)

25X9




An unidentified object is in the center and four ground scars, each approximately 900 feet long, radiate from it. These scars are oriented on azimuths of 70/250 degrees and 160/340 degrees, [REDACTED] They bisect at right angles. Several small structures are associated with this facility.

25X1D

An electronic facility is located approximately 4,500 feet southeast of the launch site in a cleared area approximately 1,200 feet square.

The site support facility consists of an administration/housing section and a housing section. The administration/housing section, located approximately 1,500 feet northeast of the



25X1D

FIGURE 2. LAYOUT OF LAUNCH AREA A.

TOP SECRET CHESS RUFF

launch site, contains 11 large barracks-type buildings, 2 smaller barracks-type buildings, a large administration building, and 7 smaller buildings. There are several excavations apparent on the north end of this section. The housing section, located approximately 3,200 feet south of the launch site, contains 10 barracks-type buildings and 6 smaller buildings.

### LAUNCH AREA B

Launch Area B (53-48N 35-47E), located in a wooded area 9.0 nm south of the complex support facility, consists of a completed Type IIC launch site and a site support facility (Figure 3). Scarring for construction was evident in [REDACTED]. The area cannot be negated. Site construction was considered com-

25X1D




FIGURE 3. LAUNCH AREA B.

NPIC/R-245/64


25X1D  
25X1D

plete in [REDACTED] Ground snow cover in [REDACTED] obscures some object detail and road and launch-pad outlines.

The launch site is enclosed by security fencing. Each launch pad is flanked by two bunkers, and a tower-like structure projects from the left and larger bunker on the side adjacent to the pad. Three other possible bunkered objects are positioned left of the center service road, between the pads. There also are five unidentified objects outboard of the right pad, one of which appears to protrude from the bunker.

An earth-banked missile-ready building is located in line with and approximately 800 feet behind each pad. These ready buildings apparently are connected to their pads by four snow-cleared tracks which exit the ready building and appear to converge between the building and the pad. No tracks can be identified on the pads. In addition, there is one building located just to the right of the center service road and one behind the right ready building.

25X9



25X1D

An electronic facility is located approximately 3,000 feet southeast of the launch site, in a cleared area approximately 1,200 feet square. There is an unidentified object in the center and four ground scars, each approximately 900 feet long, radiating on azimuths of 70/250 degrees and 160/340 degrees. These scars bisect at right angles. Several small structures are associated with this facility.

The site support facility consists of an administration/housing section and a housing section. The administration/housing section,

located approximately 2,000 feet south-south-east of the launch site, contains 4 large barracks-type buildings, 6 administration-type buildings, a long, narrow building, and 22 other buildings of various smaller sizes. The housing section contains 11 large barracks-type buildings and is located approximately 4,500 feet south-south-east of the launch site.

#### LAUNCH AREA D

Launch Area D (53-54N 35-51E) consists of a completed Type IIC launch site and a site support facility located in a wooded area 3.0 nm south-southeast of the complex support facility (Figures 4 and 5). First evidence of construction was in [REDACTED]. The area cannot be negated due to cloud cover on previous missions. The site was considered complete in [REDACTED] but ground snow cover obscures road and launch-pad outlines and some object detail.

25X1D

25X1D

The launch site is enclosed by security fencing. Each launch pad is flanked by two bunkers, and a tower-like structure projects from the left and larger bunker on the side adjacent to the pad. Three other possible bunkered objects are positioned left of the center service road, between the pads, and a smaller possible bunkered object and an undefined object are apparent forward of the right pad.

An earth-banked missile-ready building is located in line with and approximately 800 feet behind each pad. These ready buildings apparently are connected to their pads by 4 snow-cleared tracks which exit each ready building and appear to converge between the building and the pad. No tracks can be identified on the pads. In addition, there is one building just to the right of the center service road.

25X9



25X1D

FIGURE 4. LAUNCH AREA D.

25X9

25X1D  
25X1D

An electronic facility is located approximately 4,000 feet east of the launch site in a cleared area approximately 1,200 feet square, with an unidentified object in the center. Four ground scars radiate from the center on azimuths of 70/250 degrees and 160/340 degrees.

These scars are each approximately 900 feet long and bisect at right angles. Several small structures are associated with this facility.

The site support facility consists of an administration/housing section and a housing

section. The administration/housing section is located approximately 2,000 feet southwest of the launch site and contains at least 26 buildings. Six are large barracks-type buildings, one is U-shaped, and another is a large administration-type. The remaining buildings are smaller. Three small excavations are apparent at the southeast end of the administration/housing section. The housing section, located approximately 4,500 feet southwest of the launch site, consists of 8 large barracks-type buildings and 26 smaller buildings.

There is also a group of 4 large barracks-type buildings and 4 smaller buildings approximately 3,000 feet northwest of the launch site, along the access road.

NPIC/R-245/64




FIGURE 5. LAYOUT OF LAUNCH AREA D.

NPIC H-0070 (2/64)

#### REFERENCES

##### PHOTOGRAPHY

##### MAPS OR CHARTS

1. US Air Target Chart, Series 200, Sheet 0167-14A, 1st ed, Nov 58, scale 1:200,000 (SECRET)

##### DOCUMENT

1. NPIC, R-247/63, ICBM Launch Complex, Anzelsk, USSR, Nov 63 (TOP SECRET CHESSE RUFF)

##### REQUIREMENT

PC 206-64

##### NPIC PROJECT

N-259/64

TOP SECRET CHESSE RUFF